

WENTWORTH GL HOME - CONSTRUCTION SPECIFICATIONS

Builder Clearview Properties, LLC 1037 Hinesburg Road, Suite A South Burlington, VT 05403 Homeowner/Project

Clearview #

Specification Date: 6/18/2021 Site Plan Date: 3/5/2021 Plan Date: 6/17/2021

Wentworth Plan: One story home with unfinished lower level. Approximately 1,490 square feet of living space; 1,490 square feet of unfinished Lower Level, 462 square foot 2-car garage, and a 54 square foot front porch.

Location Total Square Feet First Floor 1,490

Total Finished Square Feet 1,490
Lower Level 1,490
Garage 462

54 Front Porch **Personal Choice Lists** PCL# **Date Color Code GRAPE ORANGE** GOLD **GREEN BLUE PURPLE PINK** RUST **HUNTER SKY BLUE LAVENDER BROWN NAVY** LIME **CRANBERRY AQUA PEACH** RED

Specification and Appendix Approval

Appendix A: Window Schedule
Appendix B: Exterior and Interior Door Schedule
Appendix C: Lighting Schedule
Appendix D: Plumbing Schedule
Appendix E: Finish Hardware Schedule
Appendix F: Flooring Schedule
Appendix G: Appliance Schedule

Client		Date
Client		Date
Builder	Collin Frisbie	Date



	WENTWORTH GL HOME - CONSTRUCTION SPECIFICATIONS	
Section	Information	Image
ermits		
	Builder responsible to obtain all necessary permits including:	
	- Soil Erosion and Sediment Control	
	- Zoning	
urveys		
	Home is to be staked by builder	
ite Clearing		
	Builder is responsible for all site clearing, as needed	
Itilities Connections	Daniel is responsible for all size diedinig, as needed	
	Builder responsible for all site work and site balance to include	
Water	Connection to City of Milton water system	
Sewer	Connection to City of Milton sewer system	
Gas	Connection to Natural Gas lines at road.	
Power	Underground power	
Cable	Cable TV conduit to house	
Capie	All excavation, fill and labor is included	
norgy Packago	All excavation, fill and labor is included	
nergy Package	Home to be built to VT Residential Building Energy Standards (RBES)	
Hawa ta Individa	Compliant with Act 250 Stretch Code	
Home to Include	Democratic M/history like IM Fore / Light - Quiet - Creet Verstileties - Colution - 14.0 CFM Deth. Fore / Light	
	Panasonic WhisperLite™ Fan/Light - Quiet, Spot Ventilation Solution, 110 CFM Bath Fan/Light.	
	Vented to the outside	
	Additional caulking and air sealing of joists to reduce air infiltration into the home, including	
	shoe plate; windows; and where wires and pipes go to cold spaces	
	R-15 Rigid Thermax insulation on Interior of Lower Level - floor to top of concrete wall	
	Selected use of closed cell foam to improve overall air sealing of attic in home	
	Blower Door Test as home completed required for VT RBES	
Solar Prep	Home solar ready with conduit running from LL up to Attic Space	
oundation		
Туре	Poured Concrete	
Wall Height	8'	
Lookout Height	4' Frost Wall	
Strength	Min. 3000 PSI @2 days with steel reinforcement	
Footer	Continuous 8" x 16" reinforced	
lat Work Concrete		
Lower Level	Poured Concrete	
Finish	Smooth	
"Keyway" Joints	Saw cut	
Thickness	4"	
Strength	House: Min. 3000 PSI @ 28 days Garage: Min. 4000 PSI @ 28 days	
	Tarred damp proofing membrane sprayed on exterior of foundation walls.	
Moisture Barrier	6 mil poly under concrete house slab.	
	Footing drains installed below footers around Lower Level and drained to daylight in back yard.	
Ground water controls	Drain tile buried in clean stone; covered with mirafi fabric; clean sand fill against foundation. Site	
	graded to shed surface water away from house.	
	Boulder rock walls as needed for the grading of the yard.	
Rock Wall	Boulders from the site are machine-placed to create walls.	
Priveway/Entrance	positions from the site are machine-placed to deate walls.	
	12" thick gravel two car driveway on top of mirafi fabric.	
Drive	Driveway to be finish paved with 2" of compacted asphalt.	
	Driveway to be minsh paved with 2 of compatted aspiralt.	
Walkway	42" Sidewalk from front porch to driveway	



Frame		
Exterior Walls	2x6 SPF 24" o.c.	
Interior Walls	2x4 SPF 24" o.c.	
Plate Height	9'-1" on first floor; 8'-1" on second floor and 8' in lower level	
Plate	2x6 treated southern yellow pine with foam sill seal	
Floor Framing	2x10 SPF 19.2" o.c.	
Sub Flooring	3/4" 4x8 T&G OSB glued and nailed	
	2 or 3 ply 2x12, nailed and glued, as specified by engineering load design, supported by 3-1/2"	
Girders	concrete filled lally columns in Lower Level	
Sheathing	7/16" 4x8 OSB	
Roof	Pre-engineered roof trusses 24" o.c. 5/8" T&G OSB rated sheeting	
	Pitches: 8/12 at Main House; 8/12 at Front Porch; 5/12 at front of Garage; 6/12 at Garage taper;	
Roof Pitch	6/12 at rear of Garage	
House Wrap	Professional house wrap with flashing around all windows and doors	
Roofing		
	Ice and water shield on eaves and valleys. Vented on ridge to achieve proper ventilation.	
Underlayment	Owens Corning ProArmor Synthetic Roof Underlayment	
Shingles	Owens Corning TruDefinition Shingles Limited Lifetime Warranty	
Color	Black	
Siding/Exterior Elements		
Siding	Norandex Woodsman Select	
Gable Ends	Vinyl Shakes, Color to selected by owner	
Clapboard	Double 4", Color to be selected by owner	
Board and Baton	None	
Eaves	Two piece aluminum wrapped - White	
Soffit	Perforated soffit for proper venting	
Corners	6" White Vinyl Corners with Foam Backer	
Trim Details	Frieze board and Garage Door Trim to be PVC	
Drip Edge	Galvanized	
Shutters	Available as Option	
Gutters & Downspouts	, manage as option	
Gutters & Downspouts	White Seamless Gutters	
Windows		
	See Appendix A: Window Schedule	
Brand	Harvey Slimline	
Color	White	
Construction	Vinyl, Low-E, Insulated Double-Pane	
Exterior Casing	J Channel Only (Brickmould)	
U-Factor	0.30	
Grills	Grills Between Glass 6 over 0	
Screens	Fiberglass Mesh	
Exterior Doors	,	
	See Appendix B: Exterior and Interior Door Schedule	
Brand	Therma-Tru	
Color	See Exterior Paint Section	
Construction	Insulated Fiberglass	
Exterior Casing	5/4x4 Flat	
Storm Doors	None	
Overhead Garage Doors		
Model	8300 Series Insulated Steel Door	
Size	16' x 7'	
Design	Colonial Raised Panel Door	
Color	Manufacturer White	
Opener	8" lift master 1/2 horsepower electric opener	
Remotes	2 remotes included	
Frame Key Pad	Keyless entry punch pad	
	to the state of th	



Decks & Porches		
Covered Entry Porch		
Porch Framing	6' x 9' framed with PT 2x8 joists	
Decking	5/4x6 PT decking	
Decking	3/4x0 F1 decking	
Posts	PVC wrapped and PT 6x6 Posts, 2x8 roof beams - White. Posts wrapped top and bottom.	
Roof	Roof to be truss framed, roof shingles to match house	
Ceiling	White vinyl bead board	
Stairs	Stairs from porch to walkway to be PT box steps with 5/4x6 PT treads.	
Rail	Pressure treated rail and balusters	
Finish	Porch posts, beams, PT rim board and stair risers	
Color	Porch decking and stair tread stained with Total Wood Preservative - Selected by Owner	
Deck	14' x 12' Deck Available as Option	
Exterior Paint		
Exterior Doors - Excluding Front Door	Painted Satin Finish, White	
Exterior Trim - Including Frieze Board and Door Surrounds	Painted Satin Finish, White	
Front Door	2 coats Exterior Paint, Color to be Selected by Owner	
Sidelight	Painted Satin Finish, White	
Front Porch Rail	Pressure Treated - painted white	
Front Porch Posts	Painted White	
Front Porch Roof Beams	Painted White	
Front Porch Rim board	Stained. Color to be Selected by Owner.	
Front Porch Stair Risers	Stained. Color to be Selected by Owner.	
Front Porch Decking	Stained. Color to be Selected by Owner.	
Electrical & Low Voltage	Stanical color to be selected by owner.	
	Underground electrical service, 40 circuit 150 AMP Panel with Surge Protection. Open double	
	slot for future solar.	
Plugs and Switches	SIGN TO TOUR CONTROL	
Switch Style	Toggle	
Plate Style	Toggle screw on plates	•
Switch Color	White	
Dimmers	Available as Option	
		T)
Exterior Plugs	Per Electrical Plan	
Lighting	Con Linksing Sinish Cohodula (Annuardia Collinha Sinarra Cohodula)	
Lighting Fixtures	See Lighting Finish Schedule (Appendix C: Light Fixtures Schedule)	
Recessed Lights	13 Click Lights: Kitchen 4, Front Porch 2, Main Hallway 3, Mudroom 2, Hall to Owner's Bedroom 2	
Under Cabinet Lighting	Available as Option	
Miscellaneous		
Outlets	GFI protection for all interior and exterior 240-volt outlets. 120 volt outlets in future finished areas of basement. Minimum of 2 Island Outlets. Per Electrical Plan.	
Door Chime	Nutone BK125LWH: One 2-note, white door chime	
Smoke/CO2	1 CO/Smoke per floor (1 Total), 1 Smoke per bedroom (2 Total) - Kidde 120V Intelligent 10 Year Lithium Battery Smoke Alarm Model P4010ACS	
Bath Vents	Panasonic WhisperLite™ Fan/Light - Quiet, Spot Ventilation Solution, 110 CFM	
Paddle Fan Boxes	Paddle fan rated boxes in all Bedrooms, Dining room, and Living room	
Cat 5 (data/phone)	Yes, per electrical plan	
TV Jacks	Yes, per electrical plan	
Security/Surveillance	None	
Central Vacuum	None	
Audio	None	
Solar Prep	Conduit running from LL up to Attic Space	
Garbage Disposal	Available as Option	
Light Fixtures	Available as Option	
EIGHT FIXENCES	See Appendix C: Light Fixture Schedule	
	Jee Appendix C. Light Fixture Schedule	



	Plumbing	
Heating and Venting		
Furnace	York LX Series, TM9V	
Furnace Size	40,000 BTU	
Efficiency Rating	96%	
Zones	Zone 1: First Floor	72
Second Zone	Available as Option	
Air Conditioner	Available as Option	ecotore
Thermostat	Ecobee Thermostat; First Floor	
Bath Venting	Panasonic WhisperLite™ Fan/Light - Quiet, Spot Ventilation Solution, 110 CFM Bath Fan/Light. Vented to the outside	
Dryer Venting	Microwave/Hood Vent vented to the outside	
Gas		
Main Kitchen Range	Yes	
Main Fireplace	Available as Option	
Floor Dryer	No	
Furnace	Yes	
Hot Water System	Yes	
Grill Line at Deck	Available as Option	
Fireplace and Mantle		
Fireplace in Living Room	Available as Option	
Model		
Mantle		
Tile Surround		
Tile Hearth		
Venting		
Plumbing Fixtures	Constant of the Department of the stude	
Miscellaneous Plumbing	See Appendix D: Plumbing Schedule	
Miscellaneous Plumbing		
Outdoor Faucets	2 Frost-Free Hose Bibs, located at back of the main house and on the side of the front porch	
Hot Water Heater	State 50 Gallon Hybrid Electric water heater	
Laundry	Washer Box Valve with single handle shutoff and drain; appliances pricing optional	
Plumbing	PVC Drainage plumbing.	
	PEX continuous piping for all domestic water.	
	All plumbing installed according to National Plumbing Code by licensed plumber.	
Radon	Radon Piping runs from under Lower Level concrete slab through roof.	
	This is a passive system, no fan.	
Utility Sink	Available as Option	



	Cabinets & Countertops	
Cabinets		
Kitchen		
Brand	Mid Continent Pivot Series	V.
Style	Simple F/O Style in Maple	
Color	Natural	
Kitchen Island	Natural	
Brand	Mid Continent Pivot Series	
Style	Simple F/O Style in Maple	
Color	Natural	A 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Owner's Bath	Natural	N. C. Consul
	73" Vanitu with 2 havels	
Size	72" Vanity with 2 bowls	
Brand	Mid Continent Pivot Series	
Style	Simple F/O Style in Maple	
Color	Natural	
Bath #2		建立成立
Size	42" Vanity with single bowl	V
Brand	Mid Continent Pivot Series	
Style	Simple F/O Style in Maple	
Color	Natural	
Countertops		
Kitchen		
Style	Classic Series Quartz	
Color	To Be Selected by Owner	
Edge Detail	Pencil Edge	
Cut-Outs	Under Mount Sink	
	4" Laminate	
Backsplash		
B/S Location	Perimeter Back Only	
Kitchen Island		
Style	Classic Series Quartz	
Color	To Be Selected by Owner	
Edge Detail	Pencil Edge	
Cut-Outs	None	Kitchen Tops (not color or Style)
Owner's Bath		
Style	Cultured Marble with 2 integrated flush rectangle bowls	70
Color	Cotton White	
Edge Detail	Square Edge	AM
Cut-Outs	None	
Back Splash	4" integral Cultured Marble	
B/S Location	Back Only	
Bath #2	Dack Offiy	
	Cultured Markle with 1 integrated flush restands besule	
Style	Cultured Marble with 1 integrated flush rectangle bowls	
Color	Cotton White	
Edge Detail	Square Edge	
Cut-Outs	None	
Back Splash	4" integral Cultured Marble	
B/S Location	Back Only	
	Wall & Trim Interior Detail Work	
Insulation		
Exterior Walls	R-21 6" Fiberglass Batts with Poly Vapor Barrier	
Interior Walls	R-13 3-1/2" Fiberglass Batts for bath walls (Soundproofing)	
Rigid Insulation	Box sill in first and second floor joists insulated with rigid insulation	
Attic	R-60 Cellulose with backer boards at eves for ventilation	
Garage	Not insulated	
Foundation	2-1/2" R-15 Thermax glued to concrete wall	
Drywall	TE TIE INCIDENTIAN BINCH TO CONCIETE MAII	
-	1/3" Shoot Book taned with 2 costs of joint compound at wells and sailings	
Living area walls	1/2" Sheet Rock, taped with 3 coats of joint compound at walls and ceilings	
Ceilings	Smooth Finish, minor shadow variations are possible in ceilings	
Garage	Unfinished	
Trim Details		
Casing	2-1/2" Colonial Casing	
Base	3-1/2" Colonial Base Board	H E
Wainscot	+/-60" High Wainscot at Mudroom under Black Metal Coat Hooks	
vvairiscot	17 00 Thigh Walliscot at Maaroom ander Black Metal Coat Hooks	



Built - Ins		
	Bench, Coat Hooks, Cubbies in Mudroom	2
Mirrors		
Owners Bath	Plate Glass mirror with ground edge, no bevel	
Bath #2	Plate Glass mirror with ground edge, no bevel	
Interior Stairs/Railing		
Main to Lower Level	Carpet Grade Stairs	
	Rail on wall stained	
	Half wall, cap stained to match wood floor	
Handrail Brackets	Satin Nickel	
Closet Shelving		
	All closets systems will be vented wire and the system is indicated on the plan.	
	See Closet Plan for Details.	
Interior Paint		
Painted Interior Walls	1 coat primer	
rainted interior wans	2 coats Low VOC Flat Latex Paint, Color to be selected by owner.	
Accent Wall	None	
Ceilings	To match walls	
Interior Trim	Painted, 1 coat primer, 2 coats Semi-Gloss Latex Paint,	
interior rimi	Color to be Selected by Owner, OK to Color Match	
Wainscot	Painted, 1 coat primer, 2 coats Semi-Gloss Latex Paint,	
Wainscot	Color to be Selected by Owner, OK to Color Match	
Interior Doors	Painted, 2 coats of Semi-Gloss Latex Paint, Color to be Selected by Owner, OK to Color Match	
Fireplace Mantle (optional)		
Main to Lower Level Stairs	Stained railing to Match Wood on First Floor	
Interior Doors		
	See Door Appendix B: Exterior and Interior Door Schedule	
Finish Hardware		
	See Appendix E: Finish Hardware Schedule	
Flooring		
	See Appendix F: Flooring Schedule	
Appliances		
T	See Appendix G: Appliance Schedule	
Landscaping	All disturbed gardings of country to be seeded	
	All disturbed portions of yard to be seeded.	
Lawn	Lawn area will generally include front yard, side yard and rear yard.	
0.5 1 5. 1	Lawn area to be covered with approximately 4" of native topsoil.	
		<u> </u>
	To be Selected by Owner, See Landscape Plan	
Cleaning	House classed prior to clasing including washing of windows	
Marranty	House cleaned prior to closing, including washing of windows	
vvarranty	Clearview Properties LLC Warranty as nor contract	
	Continuing a policy of constant research and improvement, Clearview Properties, LLC reserves the right to make substitutions and specification changes.	
8 Foundation Shrubs 8 Perennial Flowers Cleaning Warranty	To be Selected by Owner, See Landscape Plan To be Selected by Owner, See Landscape Plan House cleaned prior to closing, including washing of windows Clearview Properties, LLC Warranty as per contract Continuing a policy of constant research and improvement, Clearview Properties, LLC reserves	